Home Interior Design Studio, We listen we create you enjoy

# GALAXY INTERIORS

Opp : Eagle Statue siddipet Contact No : ☎9652595384,9063909628

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Project ID | | | | | | | 109605 |
| Client Name | Mr. Srijan mama | | | | | | |
| Address | | | | | | | |
| City | hyd | | | | | | |
| Quote - Date | | | | | | | July/23/2025 |
| Item | Specification | Length | Breadth | AREA | QTY | Cost | Price |
| **Kitchen** | | | | | | | |
| Plat form Frame | Hdhmr 1.5 mm Acyrlic | 20 | 2.6 | 52 | SFT | 1,350 | 70,200 |
| Upper Loft | Hdhmr 1.5 mm Acyrlic | 20 | 2.6 | 52 | SFT | 1,350 | 70,200 |
| Middel Loft Box | Hdhmr 1.5 mm Acyrlic | 12 | 2 | 24 | SFT | 1,800 | 43,200 |
| Profile box | Hdhmr 1.5 mm Acyrlic | 1 | 9 | 9 | SFT | 2,000 | 18,000 |
| Pantry unit | Hdhmr 1.5 mm Acyrlic | 3 | 7 | 21 | SFT | 1,350 | 28,350 |
| Tandoms (3) | | | | | | | 20000 |
| **Hall** | | | | | | | |
| Tv | Centuryply 1mm Laminate | 9.4 | 9 | 84.6 | SFT | 1,200 | 1,01,520 |
| Counter Top | Centuryply 1mm Laminate | 3 | 2.6 | 7.8 | SFT | 1,200 | 9,360 |
| Pooja box | Centuryply 1mm Laminate | 3 | 7 | 21 | SFT | 1,800 | 37,800 |
| Crockery Plat from | Centuryply 1mm Laminate | 2.6 | 2.6 | 6.76 | SFT | 1,800 | 12,168 |
| Crockery Upper | Centuryply 1mm Laminate | 6.6 | 2.6 | 17.16 | SFT | 1,800 | 30,888 |
| Foot stand | Centuryply 1mm Laminate | 4 | 2.6 | 10.4 | SFT | 1,200 | 12,480 |
| **Children Bedroom** | | | | | | | |
| Bunk Bed 1 | Centuryply 1mm Laminate | 3 | 6.6 | 19.8 | SFT | 1,200 | 23,760 |
| Bunk Bed 2 | Centuryply 1mm Laminate | 3 | 6.6 | 19.8 | SFT | 1,200 | 23,760 |
| Steps Bunk bed | Centuryply 1mm Laminate | | | | | | 18,000 |
| Study table | Centuryply 1mm Laminate | 6 | 2.6 | 15.6 | SFT | 1,200 | 18,720 |
| Study Storge Box | Centuryply 1mm Laminate | 6 | 6 | 36 | SFT | 1,200 | 43,200 |
| Wardbode | Centuryply 1mm Laminate | 3.3 | 6 | 19.8 | SFT | 1,200 | 23,760 |
| Wardbode Loft Upper | Centuryply 1mm Laminate | 9.6 | 2 | 19.2 | SFT | 1,200 | 23,040 |
| **Guest Bedrooms** | | | | | | | |
| Wardbode Glass | Centuryply 1mm Laminate | 5.9 | 7 | 41.3 | SFT | 1,800 | 74,340 |
| Wardbode Drews | Centuryply 1mm Laminate | 5.9 | 2 | 11.8 | SFT | 1,200 | 14,160 |
| Bed With Side tables | Centuryply 1mm Laminate | 6 | 6.6 | 63 | SFT | 1,200 | 75,600 |
| Dressing | Centuryply 1mm Laminate | 3 | 1 | 3 | SFT | 1,200 | 3,600 |
| Study table | Centuryply 1mm Laminate | 2.6 | 3 | 7.8 | SFT | 1,200 | 9,360 |
| **Master Bedrooms** | | | | | | | |
| Wardbode | Centuryply 1mm Laminate | 7.2 | 9 | 64.8 | SFT | 1,200 | 77,760 |
| Bed With Side tables | Centuryply 1mm Laminate | 6 | 6.6 | 63 | SFT | 1,200 | 75,600 |
| Dressing | Centuryply 1mm Laminate | 2 | 1 | 2 | SFT | 1,200 | 2,400 |
| **Others** | | | | 692.62 | | | |
| Transport & Loading | | | | | | | 25,000 |
| Wood Materials | NOTE : CENTURY CLUB & 1 MM LAMINETD , ALL MATERIAL BRANDED | | | | | | |
| Hardware Materials | HITTECH | | | | | | |
| Kitchen Accessories | 3 BASKETS | | | | | | |
| **Ceiling** | | | | | | | |
| Hall & Kitchen | GYPROC Board 0.5 Cage ( | 27 | 10.6 | 286.2 | SFT | 80 | 22,896 |
| Duining | GYPROC Board 0.5 Cage ( | 9.8 | 10 | 98 | SFT | 80 | 7,840 |
| Children Bedroom | GYPROC Board 0.5 Cage ( | 12 | 10 | 120 | SFT | 80 | 9,600 |
| Guest Bedroom | GYPROC Board 0.5 Cage ( | 11 | 12.6 | 138.6 | SFT | 80 | 11,088 |
| Master Bedroom | GYPROC Board 0.5 Cage ( | 11.4 | 13.4 | 152.76 | SFT | 80 | 12,221 |
| RFT Cutting | | | | 350 | SFT | 80 | 28,000 |
| **Balcony Fluted** | | | | | | | |
| PVC Children | Fulted | 5.6 | 12.6 | 70.56 | SFT | 180 | 12,701 |
| PVC Guest Bedroom | Fulted | 6 | 6.6 | 39.6 | SFT | 180 | 7,128 |
| PVC Master Bedroom | Fulted | 12.6 | 5.3 | 66.78 | SFT | 180 | 12,020 |
| PVC Hall | Fulted | 10.3 | 5.3 | 54.59 | SFT | 180 | 9,826 |
| Transport & Loading | | | | | | | 0 |
| **Electrical for Ceiling** | | | | | | | |
| Havalls Cable &Ceiling Light (450/-) 40pic & profile Light (450sft) ( Havalls) | | | | | | | 1,00,000 |
| | | | | | | | |
| **Total** | | | | | | | **₹1,219,546** |
| **NOTE :** NO CIVIL WORKS , WALL PAPERS & GLASS WORK NOT INCLUDE IN ESTIMATION . | | | | | | | |
| **Final Price** | | | | | | | |
| NOTE:KITCHEN ACCESORIES NOT INCLUDED IN THIS QUOTATION,ADDITIONAL PRICE WILL BE ADDED AS PER YOUR SELECTION. | | | | | | | |

## Summary of Material details:

| | |
|---|---|
| **Laminates :** | **1 MM Upto 2000/- Any Brand. Inner Laminate ( Fabric 0.8 mm)** |
| **Slidings Doors :** | **18mm block bord for all doors,** |
| **Fevicol :** | **Marine , Sliding tracks : Hittech & Nimmi** |
| **Hardware :** | **Hinges: Soft Close Hittech indian** |
| **Sliding tracks :** | **Soft Close** |
| **HANDLES :** | **Sliding Handles @500/- , Doors Handles @150/-** |
| **PAYMENT :** | **10% Singup payment , 50% in production, 30% before lamintion,10% before handover** |
| **NOTE :** | **Any Extra work will be added as per sft price , Any add ons will be charged in Laminates or Hardware as per cost.** |